

## SUMMARY OF QUANTITIES

**PROJECT: 773-V-4335; Bridge on 375th Street West over South Fork  
Ninnescah River (B547)**

**TYPE OF WORK: Bridge Overlay**

Bidding Item	Approx. Quantity	Unit
Field Office	1	Each
Mobilization	1	L.S.
Contractor Construction Staking	1	L.S.
Removal of Existing Structures	1	L.S.
Machine Preparation (1 1/2)	1,670	Sq. Yds.
Area Prepared for Patching	167	Sq. Yds.
Area Prepared for Patching (Full Depth)	84	Sq. Yds.
Portland Cement Concrete Overlay (1 1/2")	1,670	Sq. Yds.
Material for Portland Cement Concrete Overlay (Set Price)	1	Cu. Yds.
Reinforcing Steel (Gr. 60)(Repair)(Set Price)	1	Lbs.
Bridge Deck Grooving	1,413	Sq. Yds.
Traffic Control	1	L.S.
Methyl Methacrylate Pavement Marking (White)(6")(0.080")	1,165	Lin. Ft.
Methyl Methacrylate Pavement Marking (Yellow)(4")(0.080)	1,165	Lin. Ft.