

SUMMARY OF QUANTITIES

PROJECT: 802-BB-1188; Diagonal Road Over a Tributary to the Ninnescah River (B516)

TYPE OF WORK: Grading, Surfacing, RFB, Seeding, Signing, Pavement Marking

Bidding Item	Approx. Quantity	Unit
Contractor Construction Staking	1	LSUM
Field Office	1	EA.
Mobilization	1	LSUM
Removal of Existing Structures	1	LSUM
Clearing and Grubbing	1	LSUM
Common Excavation	1143	C.Y.
Rock Excavation	441	C.Y.
Compaction of Earthwork (Type B) (MR-90)	1409	C.Y.
Common Excavation (Contractor Furnished)	514	C.Y.
Water (Grading) (Set Price)	1	MGAL
Aggregate Base (Special) (6")	2662	S.Y.
Water Aggregate Base (Grading) (Set Price)	1	MGAL
Plant Mix Asphalt Mixture (Commercial Grade)	839	TON
Aggregate Shoulder (AS-1) (6")	511	S.Y.
Water (Aggregate Shoulder) (Set Price)	1	MGAL
Slope Protection (Riprap Stone)	74	C.Y.
Cross Road Pipe (24') (RCP)	171	L.F.
End Section (24") (RC)	3	EA.
Concrete (Grade 4.0)	131.4	C.Y.
Concrete (Grade 4.0) (AE)	110	C.Y.
Bridge Backwall Protection System	360	S.Y.
Reinforcing Steel (Grade 60)	1312	LBS.
Reinforcing Steel (Grade 60) (Epoxy Coated)	41333	LBS.
Class III Excavation	350	C.Y.
Foundation Stabilization	79	C.Y.
Concrete for Seal Course (Set Price)	1	C.Y.
Traffic Control	1	LSUM