

SUMMARY OF QUANTITIES

PROJECT: Construction Plans; Four Oaks Street

TYPE OF WORK: Grading, Asphalt Paving, Stormwater, Signing, Seeding

Bidding Item	Approx. Quantity	Unit
Mobilization	1	LS
Contractor Construction Staking	1	LS
Clearing and Grubbing	1	LS
Traffic Control	1	LS
Temporary Seeding	1	LS
Seeding	1	LS
Common Excavation (Rural Small)	2922	CY
Compaction of Earthwork (Type B)(MR-90)	173	CY
Water (Grading)(Set Price)	1	MGAL
Plant Mix Asphalt Mixture Commercial Grade (6")	2136	TONS
Aggregate Base (Special)(6")	6395	SY
Water (Aggregate Base)(Set Price)	1	MGAL
Water (Aggregate Shoulder)(Set Price)	1	MGAL
Aggregate Shoulder (AS-1)(6")	1015	SY
Sign (Remove and Reset)	1	LS
Mailbox Installation (Set Price)	8	EA
Entrance Pipe (18")(RCP)	182	LF
Cross Road Pipe (24")(RCP)	146	LF
Cross Road Pipe (36")(RCP)	44	LF
End Section (18")(RC)	14	EA
End Section (24")(RC)	6	EA
End Section (36")(RC)	2	EA
Erosion Control (Class 1, Type Y)	151	SY
Sediment Removal (Set Price)	1	CY
Biodegradable Log (12")	450	LF
SWPP Design	1	LS

